

ADDENDUM NO.1
Nisqually Indian Tribe
PROJECT # PARKS 15-02

Changes from the original RFP are highlighted below in yellow and are now hereby incorporated into the bidding documents for the Nisqually Parks Kiosk project.

Project Summary:

- Earthwork and earth moving as needed to install concrete pad to specifications.
- Include removal and lawful disposal of excess dirt.
- Concrete pad with support footing for the kiosk umbrella-type roofing.
- The support beams are of steel interior with decorative, turned cedar log wrapping, to be stained in a clear finish. SHEEN SELECTED BY OWNER.
- **The roof will be a 25 gauge vertical seam, with 12" span, metal roof with a red color.** COLOR SELECTED BY OWNER. The roof trim will also metal, with a black color selected by the Owner. Roof shall be installed to meet the manufacturer's requirements and warranty requirements. Interior panels are to be of exterior grade plywood.
- Paint in an exterior paint finish. THREE COLOR SELECTIONS CHOSEN BY OWNER.
- OWNER to supply and install signage.
- All work shall meet Pierce County building permit and inspection requirements.